WEST BENGAL RENEWABLE ENERGY DEVELOPMENT AGENCY
(An Organization of Dept. of NRES, Govt. of West Bengal)
Bikalpa Shakti Bhawan, Plot no.: J1/10, EP & GP Block, Sector-V,
Electronics Complex Salt Lake, Kolkata – 700091
Phone: 033-23575038 / 23575348 / 23576568

Notice Inviting Quotation

Memo No: WBREDA/ Interior/354 Date: 09-07-2024

Quotation No: WBREDA/Tech/Q-21 Date: 09-07-2024

1. Sealed quotations are invited from reliable and experienced contractor for the work of as per schedule Annexure I at the 3rdFloor of Bikalpa Sakti Bhaban, West Bengal Renewable Energy Development Agency (WBREDA), J1/10, EP & GP Block, Salt Lake Electronics Complex, Sector – V, Kolkata – 700 091. The quotation with complete details of document shall be available at the office of WBREDA.

2. **Scope of Work:** Enclosed as per schedule Annexure -I

3. **Completion Time:** 10 (Ten) days from the date of Issuance of order

4. **Important Information**

Sl. No.	Particulars	Information
01	Start Date or availability of Quotation document in the official website.	10/07/2024 at 2.00 P.M
03	Last date and time for submission of Quotation at West Bengal Renewable Energy Development Agency	18/07/2024 Up to 2.00 P.M.
04	Date and time for opening of Quotation	18/07/2024 at 3.00 P.M.
05	Address for submission of Quotation.	West Bengal Renewable Energy Development Agency, Bikalpa Shakti Bhavan, J-1/10, EP & GP Block, Salt Lake, Sector-V, Kolkata - 700091

Note: In case the last date for receipt of NIQ happens to be a holiday for WBREDA for any reason, the activity will be held on the immediate next working day at the same time & place.

WEST BENGAL RENEWABLE ENERGY DEVELOPMENT AGENCY WBREDA ESTD-1993

5. **Submission of Quotation**

a) The Quotation shall be submitted in Sealed Condition mentioning the Quotation No. and Date (WBREDA/Tech/Q-21 dated 09-07-2024), Name of the Bidder. The Quotation shall be submitted on the letter head of the bidder duly signed and stamp.
b) Quotation shall be submitted in prescribed format. If submitted in any other form the same shall be summarily rejected without assigning any reasons what so ever.
c) The quotation will not be sent by post.
d) The Rates to be quoted as percentage (%) above /below/ at per basis on the estimated amount of the work.
e) Before submitting the quotation intending tenderer may inspect the site on prior intimation.

6. **Other Terms and Conditions**

a) Superintending Engineer of WBREDA shall be the controlling officer of this work.
b) DDO, WBREDA shall be the Paying Authority.
c) In case of any query, the bidders may contact through our email-**akd.wbreda@gmail.com** or physically at Office of the WBREDA, Bikalpa Shakti Bhavan, J-I/10, EP & GP Block, Salt Lake Electronics Complex, Sector-V, Kolkata-700 091.
d) The Quotation Inviting Authority reserves the right to modify, amend or supplement the document. Any corrigendum, notification concerned to this quotation will be published in the **Notice Board** and it will be part & parcel of the quotation.
e) Payment terms: 100% payment shall be made after completion of works against submission of Bill.
f) No advance payment will be made on any account.
g) WBREDA reserves the right to accept or reject any or all quotation
h) The work shall have to be executed as per enclosed Schedule, terms and condition mentioned in the quotation. Conditional offer will not be accepted in any case.

7. **Intending bidder may collect a copy of this notice with schedule on submission of an application for submission of their offer.**

-Sd-
Superintending Engineer

Annexure-I

Schedule of work

Ref Quation No: WBREDA/Tech/Q-21 dated 09-07-2024

Renovation Work of Existing South Side Window at Hon,ble MIC,NRES Dept. Chember at 3rd Floor Level of BIKALPA SHAKTI BHAVAN (WBREDA)(UPVC Frame work with 8 mm clear glass frame 3 Track 3 sash sliding window work)

Item No.	Description	Unit	Qty	Rate	Amount
1	Providing and fixing of factory made uPVC Sliding window (White Colour) complete, (U value=1.9-1.3 W/m 2 K, flame resistant, self extinguishing, lead free) comprising uPVC multi-chambered frame having in-built uPVC roller track on top and uPVC sash with wall thickness of 2.3mm (±0.2 mm) duly reinforced with G.I. section 1.6 mm (±0.2 mm), wherever required. All corners of frame and sash will be fusion welded. After placing 8 mm coloured, toughened reflective glass conforming to IS: 2553-1992 (part-II) in the sash, uPVC glazing bead, interlock, EPDM gasket, brush shall be provided including touch lock and rollers & proper drainage system shall be provided. Window frame will be fixed to the wall with 100mm long and 8mm dia. Fasteners and after fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size, of approved quality complete in all respect as per as per approved drawing & direction of Engineer-In-Charge. (Note: Profile manufacturer & Window Manufacturer must be one & same, Only manufacturer Waranty is aceptable				
(a)	3 Track 3 Sash window frame of size 122 x 54 mm & Sash of size 64 x 47 mm both having wall thickness of 2.3 ± 0.2 mm (inclusive 18 % GST)	Sq.M	7.694	11023	₹ 84,806.55
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (3 rd floor).[Excluding cost of chipping over concrete surface](inclusive 18 % GST)				
(i)	With 1:6 cement mortar				
(a)	15 mm thick plaster	Sq.M	5	192.34	₹ 961.70
3	Protective and Decorative Textured exterior high class matt finish paint of approved quality, composed of special Tharmoplastic Resin containing fine crystalline additives derive from Granite as per manufacturer's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material,labour, scaffolding and all incidental charges but excluding the cost of primer.(at 3rd floor Level)(inclusive 18 % GST)				
(a)	Two Coat	Sq.M	5	121.72	₹ 608.60
4	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or cencrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per directionof the EIC.(inclusive 18 % GST)				
(a)	One Coat	Sq.M	5	39.56	₹ 197.80
5	Godrej Hydraulic door closer fitted and fixed complete.(inclusive 18 % GST)	each	2	2435.52	₹ 4,871.04
(a)	Heavy type				
			Total		₹ 91,445.69
	Grand Total (Inclusive 18 % GST)			**Say**	₹ **91,446**

Rupees Ninety one thousand four hundred fourty six only

WEST BENGAL RENEWABLE ENERGY DEVELOPMENT AGENCY WBREDA ESTD-2007

09/07/24

Quoted Price (Format)

To
The Superintending Engineer
WEST BENGAL RENEWABLE ENERGY DEVELOPMENT AGENCY
(An Organisation of Deptt. of NRES, Govt. of West Bengal)
Bikalpa Shakti Bhawan, Plot no.: J1/10, EP & GP Block, Sector-V,
Electronics Complex Salt Lake, Kolkata – 700091

Ref Quation No: WBREDA/Tech/Q-21 dated 09-07-2024

Renovation Work of Existing South Side Window at Hon,ble MIC,NRES Dept. Chember at 3rd Floor Level of BIKALPA SHAKTI BHAVAN (WBREDA)
(UPVC Frame work with 8 mm clear glass frame 3 Track 3 sash sliding window work)

Item No.	Description of Works	Unit	Qty	Estimated Cost	Bidder Should submit the rate for the said job in Percentage Besis (Above / Below / At per)
1	Providing and fixing of factory made uPVC Sliding window (White Colour) complete, (U value=1.9-1.3 W/m 2 K, flame resistant, self extinguishing, lead free) comprising uPVC multi-chambered frame having in-built uPVC roller track on top and uPVC sash with wall thickness of 2.3mm (±0.2 mm) duly reinforced with G.I. section 1.6 mm (±0.2 mm), wherever required. All corners of frame and sash will be fusion welded. After placing 8 mm coloured, toughened reflective glass conforming to IS: 2553-1992 (part-II) in the sash, uPVC glazing bead, interlock, EPDM gasket, brush shall be provided including touch lock and rollers & proper drainage system shall be provided. Window frame will be fixed to the wall with 100mm long and 8mm dia. Fasteners and after fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size, of approved quality complete in all respect as per as per approved drawing & direction of Engineer-In-Charge. (Note: Profile manufacturer & Window Manufacturer must be one & same, Only manufacturer Waranty is aceptable			Rs. 91446/- (Rupees Ninety one thousand four hundred fourty six only) (Inclusive 18 % GST)	In Figure ..... In Word .....
(a)	3 Track 3 Sash window frame of size 122 x 54 mm & Sash of size 64 x 47 mm both having wall thickness of 2.3 ± 0.2 mm (inclusive 18 % GST)	Sq.M	7.694		
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (3 rd floor).[Excluding cost of chipping over concrete surface](inclusive 18 % GST)				
(i)	With 1:6 cement mortar				
(a)	15 mm thick plaster	Sq.M	5		
3	Protective and Decorative Textured exterior high class matt finish paint of approved quality, composed of special Tharmoplastic Resin containing fine crystalline additives derive from Granite as per manufacturer's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material,labour, scaffolding and all incidental charges but excluding the cost of primer.(at 3rd floor Level)(inclusive 18 % GST)				
(a)	Two Coat	Sq.M	5		
4	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or cencrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per directionof the EIC.(inclusive 18 % GST)				
(a)	One Coat	Sq.M	5		
5	Godrej Hydraulic door closer fitted and fixed complete.(inclusive 18 % GST)				
(a)	Heavy type	each	2		

Declearation: We are accepting and comply all the terms and condition of the quotation vide no:WBREDA/Tech/Q-21 dated 09-07-2024

Signature with date and Seal of the Bidder